



David LeBlond  
Principal Manager, Regulatory Affairs-Wildfire & Public Safety  
[david.leblond@sce.com](mailto:david.leblond@sce.com)

Docket: 2026-2028 Electrical Corporation Wildfire Mitigation Plans  
Docket# 2026-2028-Base-WMPs  
Revision 0  
Volume 1 of 1

June 2, 2025

Tony Marino  
Deputy Director  
Office of Energy Infrastructure Safety  
715 P Street, 20th Floor  
Sacramento, CA 95814

SUBJECT: SCE's Substantive Errata for the 2026-2028 Wildfire Mitigation Plan (WMP)

Dear Deputy Director Marino:

On May 16, 2025, SCE submitted its 2026-2028 Base WMP R0 to the Office of Energy Infrastructure Safety (OEIS). Since that submission, SCE has identified certain errors that SCE seeks to correct in accordance with the OEIS Process Guidelines, Section 7, concerning errata. SCE's corrections are set forth in the table and redlines on the following pages.

SCE's 2026-2028 WMP and associated materials are available at <https://www.sce.com/wmp/>

Sincerely,  
//s//

David LeBlond  
Principal Manager, Regulatory Affairs-Wildfire & Public Safety  
[david.leblond@sce.com](mailto:david.leblond@sce.com)

## Table of Errata

The table below lists requested corrections to the May 16, 2025 submission of SCE's 2026-2028 Base WMP R0.

Section	Table or Figure (if applicable)	Page Number(s)	Description of Correction	Reason for Correction
4.3	Table 4-3	618-635	Circuits ANGUS, CORSAIR, DONLON, DYNAMO, FIREBIRD, Gabbert, LAUDA, LIMONITE, MERLIN, NAPA, PATRICIA, PETIT, PURCHASE, SAVORY, SESPE, STUBBY, TAIWAN, and TIMBER CANYON were added.	These circuits experienced multiple outages on the same date or were otherwise missing from the previous submission but do meet the criteria to be included in Table 4-3, having had 3 or more de-energizations in one of the last 6 years.
4.3	Table 4-3	618-635	Circuits DYSART and FROZEN were removed.	These circuits were previously included because they experienced outages with no customer impact, but these outages should not be included.
4.3	Table 4-3	618-635	Updated the dates of outages listed to match the date of de-energization instead of the date of PSPS events, and amended footnote [2] to reflect the change. Though not shown in redlines, the Dates of Outages were sorted from Newest to Oldest by each circuit to read more easily.	De-energization date more closely matches the field name "Dates of Outages" than event date.
4.3	Table 4-3	618-635	Added Dates of Outages for existing circuits and Number of Customers Hours of PSPS per Outage where available. Footnote [2] was updated to identify that multiple outages may exist on the same date.	Multiple outages exist for each date and should be included in Dates of Outages.

Section	Table or Figure (if applicable)	Page Number(s)	Description of Correction	Reason for Correction
6.2.1.3	Table 6-4	201-205	Updated the initiative activities listed for certain circuits by year. Additions are in red font. Removals are in red strikethrough.	Corrections to certain grid hardening initiatives associated with circuits in particular years.
7.2	N/A	211	Updated the circuit miles and count of covered conductor completed, planned, and under review. Additions are in red font. Removals are in red strikethrough.	Updated numbers align with the requested changes to Table 4-3.

**SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0**

Table 4-3: SCE Frequently Deenergized Circuits

[1] Pursuant to the guidance, SCE has only included circuits that experienced three or more deenergizations in a year for the 6 years prior to the submission of this WMP. Such circuits are not included in years in which they only experienced two or fewer deenergizations.

[2] For Date of Outage, SCE provides the ~~event~~ de-energization date. For the dates listed, multiple deenergizations may have occurred on the same date.

[3] For Customer Hours of PSPS per Outage per Circuit, SCE calculates by isolation device or segments the difference between restoration time and deenergization time in hours multiplied by the total number of customers impacted, summed for each circuit. PSPS tracking and reporting varied until 2021. As such, SCE was not able to produce comparable values of customer hours of PSPS per outage per circuit for 2019, 2020, or 2021.

[4] SCE lists here measures taken or planned to reduce PSPS impacts. This might not include all wildfire mitigations on a circuit, as some measures are taken or planned to reduce wildfire risk. For example, there may be more covered conductor, REFCL, or other system hardening performed on each circuit than listed in this table.

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
1	ED-00108	ACOSTA	<del>12/2/2020</del> 12/3/2020	Data not available	Completed: <ul style="list-style-type: none"> <li>Automated 1 existing switch</li> <li>Implemented operational protocol to raise PSPS windspeed thresholds</li> <li>Replaced 7.28 miles of existing overhead wire with new insulated wire</li> </ul>	This section requests electrical corporations to provide projections for future deenergizations and customer impacts. PSPS are a function of future weather conditions and cannot be predicted with a meaningful level of certainty. Between 2023 and 2025, SCE’s service territory saw more extreme fire weather with each subsequent year prompting an annual increase in PSPS. If in future years current trends of extreme weather and fire conditions continue, PSPS events will continue and may increase in frequency and duration as an essential mitigation to protect public safety.
			<del>11/26/2020</del> 11/27/2020			
			10/26/2020			
			10/30/2019			
			10/28/2019			
			10/24/2019			
10/10/2019						
2	ED-00452	AMETHYST	<del>12/7/2020</del> 12/8/2020	Data not available	Completed: <ul style="list-style-type: none"> <li>Replaced 1.4 miles of existing overhead wire with new insulated wire</li> <li>Installed an additional weather station to improve situational awareness</li> </ul>	
			<del>12/2/2020</del> 12/3/2020			
			<del>11/26/2020</del> 11/27/2020			
			10/26/2020			
3	ED-00560	ANGUS	11/25/2021	Data not available	Completed: <ul style="list-style-type: none"> <li>Replaced 5.66 miles of existing overhead wire with new insulated wire</li> </ul>	
			11/25/2021			
			11/25/2021			
			1/19/2021			
			<del>12/10/2024</del>	583	Completed: <ul style="list-style-type: none"> <li>Replaced 27.17 miles of existing overhead wire with new insulated wire</li> <li>Installed an additional weather station</li> <li>Installed 1 automated switch and implemented additional segmentation</li> <li>Implemented operational protocol to raise PSPS windspeed thresholds</li> </ul>	
			<del>12/9/2024</del>	1,926		
			<del>11/6/2024</del>	3,304		
			<del>12/9/2023</del>	1,328		
			<del>10/30/2023</del>	578		
			<del>10/29/2023</del>	395		
			11/25/2021			
			11/25/2021			
			11/25/2021			
1/19/2021						
				Planned Work:		

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
34	ED-01344	ANTON	1/19/2021	Data not available	<ul style="list-style-type: none"> <li>Install 1 automated switch and implement additional segmentation</li> </ul>	
			1/19/2021			
			1/17/2021			
			1/15/2021			
			12/23/2020			
			12/19/2020			
			12/19/2020			
			12/7/2020			
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			11/26/2020			
			10/26/2020			
			10/26/2020			
			10/16/2020			
			9/9/2020			
			11/17/2019			
			10/30/2019			
10/28/2019						
10/24/2019						
10/10/2019						
45	ED-00705	ARLENE	12/23/2020	Data not available	Completed: <ul style="list-style-type: none"> <li>Replaced 9.04 miles of existing overhead wire with new insulated wire</li> <li>Updated switching protocols</li> </ul>	
			12/7/2020			
			12/3/2020			
			11/26/2020			
56	ED-00817	ATENTO	<del>12/23/2020</del> 12/24/2020	Data not available	Completed: <ul style="list-style-type: none"> <li>Replaced 38.34 miles of existing overhead wire with new insulated wire</li> <li>Implemented operational protocols to raise PSPS windspeed thresholds</li> <li>Installed 3 automated switches and implement additional segmentation</li> </ul>	
			<del>12/2/2020</del> 12/3/2020			
			<del>11/26/2020</del> 11/27/2020			
			10/26/2020			
67	ED-00971	BADGER	11/25/2021	Data not available	Completed: <ul style="list-style-type: none"> <li>Replaced 1.6 miles of existing overhead wire with new insulated wire</li> </ul> Planned Work: <ul style="list-style-type: none"> <li>Replace 1.45 miles of existing overhead wire with new insulated wire</li> </ul>	
			11/21/2021			
			1/19/2021			
			12/10/2024	130	Completed:	
			11/6/2024	12,583		

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PPS of circuit [4]	Estimated Annual Decline in PPS Events and PPS Impact on Customers
78	ED-00990	BALCOM	11/6/2024	1,201	<ul style="list-style-type: none"> <li>Replaced 13.86 miles of existing overhead wire with new insulated wire</li> <li>Implemented switching protocols to transfer load to a less affected circuit</li> <li>Installed an additional weather station</li> </ul>	
			12/23/2020	Data not available		
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			10/30/2019			
			10/28/2019			
			10/24/2019			
			10/10/2019			
89	ED-01630	BIG ROCK	11/25/2021	Data not available	<p>Completed:</p> <ul style="list-style-type: none"> <li>Replaced 10.69 miles of existing overhead wire with new insulated wire</li> <li>Installed 2 automated switches</li> <li>Installed an additional weather station</li> <li>Implemented operational and switching protocols to transfer load to a less affected circuit</li> </ul>	
			1/19/2021			
			1/15/2021			
			1/14/2021			
			12/23/2020			
			12/7/2020			
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			12/3/2020			
			11/27/2020			
11/26/2020						
10/26/2020						
910	ED-03314	BIRCHIM	11/22/2024	6,683	Under engineering review for PPS grid hardening measures	
			10/28/2024	1,355		
			10/27/2024	<del>1,446</del> 115		
			10/17/2024	11,654		
			8/24/2024	21		
1011	ED-01745	BLACKHILLS	11/24/2021	Data not available	<p>Completed:</p> <ul style="list-style-type: none"> <li>Replaced 0.68 miles of existing overhead wire with new insulated wire</li> </ul> <p>Planned Work:</p> <ul style="list-style-type: none"> <li>Replace 0.05 miles of existing overhead wire with new insulated wire</li> </ul>	
			1/19/2021			
			<del>1/14/2021</del> 1/15/2021			
1112	ED-01832	BLUE CUT	12/9/2024	812	<p>Under engineering review for PPS grid hardening measures</p> <p>Completed:</p> <ul style="list-style-type: none"> <li>Replaced 40.43 miles of existing overhead wire with new insulated wire</li> </ul>	
			11/6/2024	471		
			10/18/2024	8,600		
			<del>12/2/2020</del> 12/3/2020	Data not available		

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
			<del>11/26/2020</del> 11/27/2020	Data not available	Planned Work: • Replace 10.51 miles of existing overhead wire with new insulated wire	
			10/26/2020			
			12/23/2020			
			12/7/2020			
<del>12</del> 13	ED-01954	BOOTLEGGER	12/3/2020	Data not available	Completed: • Insulated Wires: Replaced 28.82 miles of existing overhead wire with new insulated wire • Implemented switching protocol to remove some customers and critical businesses from PSPS	
			<del>11/26/2020</del> 11/27/2020			
			10/26/2020			
			9/9/2020			
			10/30/2019			
<del>13</del> 14	ED-02035	BOUQUET	10/24/2019	Data not available	Completed: • Replaced 30.23 miles of existing overhead wire with new insulated wire • Added temporary generator to serve approx. 250 customers during a PSPS event with minimal outages	
			10/10/2019			
			12/9/2023	9,991		
<del>14</del> 15	ED-02191	BRENNAN	11/20/2023	1,851	Under engineering review for additional covered conductor scope	
			10/29/2023	5,566		
			<del>12/17/2024</del> 12/18/2024	286		
<del>15</del> 16	ED-02261	BROADCAST	12/9/2024	736	Under engineering review for potential remote grid / PSPS grid hardening measures	
			11/6/2024	3,759		
			10/18/2024	493		
			11/24/2021			
<del>16</del> 17	ED-02577	CABANA	1/19/2021	Data not available	Completed: • Replaced 0.6 miles of existing overhead wire with new insulated wire	
			1/15/2021			
			12/17/2024	125	Under engineering review for PSPS grid hardening measures	
			12/9/2024	182		
<del>17</del> 18	ED-02674	CALGROVE	11/6/2024	24,087	Completed: • Replaced 5.67 miles of existing overhead wire with new insulated wire • Installed 1 automated switch • Installed an additional weather station	
			11/25/2021			
			1/19/2021	Data not available		
			1/16/2021			
			1/15/2021			
			12/17/2024	219	Under engineering review for PSPS grid hardening measures	
			12/10/2024	248		
			11/6/2024	535	Completed: • Replaced 3.04 miles of existing overhead wire with new insulated wire	
			<del>12/9/2023</del>	<del>221</del>		

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
18 19	ED-02751	CALSTATE	10/30/2023	160	Planned Work: • Install 1 automated switch	
			10/29/2023	219		
			11/25/2021	Data not available		
			11/21/2021			
			1/19/2021			
			1/15/2021			
			12/23/2020			
			<del>12/7/2020</del> 12/8/2020			
			12/3/2020			
			11/27/2020			
			10/26/2020			
			10/30/2019			
			10/30/2019			
			<del>10/29/2019</del> 10/28/2019			
			10/24/2019			
10/20/2019						
10/10/2019						
19 20	ED-02790	CAMP BALDY	<del>12/7/2020</del> 12/8/2020	Data not available	Completed: • Installed insulated wire	
			<del>11/26/2020</del> 11/27/2020			
			10/26/2020			
20 21	ED-03099	CASMALIA	10/30/2019	Data not available	Completed: • All existing overhead in HFRA was previously switched to the Impala 12kV	
			10/28/2019			
			10/24/2019			
			10/10/2019			
21 22	ED-04632	CASTRO	11/25/2021	Data not available	Completed: • Replaced 18.73 miles of existing overhead wire with new insulated wire • Installed 2 automated switches • Installed an additional weather station • Added a new switch to improve segmentation and reduce customer impacts	
			11/21/2021			
			1/19/2021			
			12/24/2020			
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			10/30/2019			
			10/28/2019			
			<del>10/23/2019</del> 10/24/2019			
<del>10/10/2019</del> 10/11/2019						
22 23	ED-03714	COBRA	12/23/2020	Data not available	Completed: • Replaced 0.24 miles of existing overhead wire with new insulated wire • Automated 2 existing switches • Installed an additional weather station	
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			



SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
23 24	ED-03885	CONDOR	1/19/2021	Data not available	Completed:  • New insulated wire has already been installed on nearly all existing overhead portions of the circuit • Replaced an additional 1.7 miles of existing overhead wire with new insulated wire near the substation	
			1/19/2021			
			1/19/2021			
			12/23/2020			
			12/8/2020			
			12/7/2020			
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			11/27/2020			
			11/27/2020			
			<del>10/29/2019</del> 10/30/2019			
10/24/2019						
10/10/2019						
25	ED-04109	CORSAIR	11/25/2021	Data not available	Completed: • Replaced 70.82 miles of existing overhead wire with new insulated wire	
			1/19/2021			
24 26	ED-04495	CUDDEBACK	12/3/2020	Data not available	Completed: • Replaced 7.53 miles of existing overhead wire with new insulated wire	
			12/2/2020			
			11/16/2020			
			10/30/2019			
			10/28/2019			
			10/24/2019			
10/10/2019						
25 27	ED-04526	CUTHBERT	12/9/2024	96270	Under engineering review for PSPS grid hardening measures (covered conductor and undergrounding)  Completed: • Installed 1 automated switch • Replaced 2.02 miles of existing overhead wire with new insulated wire • Implemented operational protocols to raise PSPS windspeed thresholds, and transfer load to a less affected circuit	
			11/6/2024	85942		
			10/18/2024	56731		
			<del>11/24/2021</del> 11/25/2021	Data not available		
			11/25/2021			
			11/21/2021			
			1/19/2021			
<del>1/14/2021</del> 1/15/2021						
26 28	ED-04596	DALBA	12/9/2024	13,344	Under engineering review for PSPS grid hardening measures	
			11/6/2024	13,795		
			10/18/2024	17,428		
			12/10/2024	20,265		
			12/10/2024	10,431	Completed:	

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
27-29	ED-04706	DAVENPORT	11/6/2024	5,674	• Replaced 41.72 miles of existing overhead wire with new insulated wire	
			1/19/2021			
			1/19/2021			
			1/15/2021			
			1/15/2021			
			12/7/2020			
			12/7/2020			
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			11/27/2020			
			11/26/2020			
			10/26/2020			
			10/26/2020			
			10/30/2019			
10/28/2019						
10/24/2019						
10/10/2019						
28-30	ED-04900	DE MILLE	<del>12/7/2020</del> 12/8/2020	Data not available	Completed: • Replaced 6.0 miles of existing overhead wire with new insulated wire • Circuit cutover to Lopez 16kV which has higher PSPS thresholds	
			12/3/2020			
			10/26/2020			
31	ED-05207	DONLON	11/25/2021	Data not available	Planned Work: • Replace 1.27 miles of existing overhead wire with new insulated wire  Completed: • Replaced 6.61 miles of existing overhead wire with new insulated wire	
			1/19/2021			
			1/19/2021			
29-32	ED-05376	DUKE	12/23/2020	Data not available	Completed: • New insulated wire on most overhead portions of the circuit within HFRA • Replaced 0.4 miles of remaining bare overhead wire within HFRA with new insulated wire • Installed 2 automated switches	
			12/7/2020			
			12/3/2020			
			12/2/2020			
33	ED-05483	DYNAMO	10/19/2019	Data not available	Planned Work: • Replace 14.24 miles of existing overhead wire with new insulated wire.	
			10/17/2019			
			9/16/2019			
			N/A		Completed:	

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
<del>30</del>	<del>ED-05483</del>	<del>DYSART</del>	<del>N/A</del>	<del>Data not available</del>	<del>• Replaced 11.61 miles of overhead bare wire with new insulated wire</del>	
<del>31</del> 34	ED-05591	ECHO	12/18/2020 <del>12/7/2020</del> 12/8/2020 10/26/2020	Data not available	Completed: • Replaced 2.2 miles of existing overhead wire with new insulated wire	
<del>32</del> 35	ED-05930	ENERGY	12/17/2024	1,351	Under engineering review for PSPS grid hardening measures  Completed: • Replaced 27.41 miles of existing overhead wire with new insulated wire  • Installed 3 automated switches and implement additional segmentation • Added temporary generator to serve approx. 120 customers during a PSPS event with minimal outages	
			<del>12/10/2024</del>	<del>53,572</del>		
			12/9/2024	<del>54,147</del> 1,476		
			<del>11/6/2024</del>	<del>51,376</del>		
			<del>11/6/2024</del>	<del>1,915</del>		
			11/4/2024	<del>53,908</del> 160		
			10/19/2024	193		
			12/9/2023	1,609		
			11/9/2023	462		
			<del>10/30/2023</del>	<del>8,397</del>		
			<del>10/30/2023</del>	<del>195</del>		
			10/29/2023	<del>22,562</del> 3,011		
			<del>10/29/2023</del>	<del>2,839</del>		
			11/25/2021			
			11/24/2021			
			11/21/2021			
			<del>10/16/2021</del>			
			10/15/2021			
			<del>10/11/2021</del> 10/12/2021			
			1/19/2021			
			1/18/2021			
			<del>1/16/2021</del> 1/17/2021			
			1/15/2021			
1/14/2021						
12/23/2020						
<del>12/20/2020</del>	Data not available					
12/19/2020						
12/7/2020						
<del>12/3/2020</del>						
12/2/2020						
11/27/2020						

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
			11/26/2020			
			10/26/2020			
			10/16/2020			
			<del>11/25/2019</del> 11/26/2019			
			10/30/2019			
			10/28/2019			
			10/24/2019			
			10/10/2019			
<del>33</del> 36	ED-06065	ESTABAN	<del>12/24/2020</del>		Completed: • Replaced 13.8 miles of existing overhead wire with new insulated wire	
			12/23/2020	Data not available		
			12/7/2020			
			<del>12/7/2020</del>			
			12/3/2020			
			<del>12/2/2020</del> 12/3/2020			
			10/30/2019			
			10/24/2019			
			<del>10/24/2019</del>			
			10/10/2019			
<del>34</del> 37	ED-06357	FERRARA	<del>12/7/2020</del> 12/8/2020			Planned Work: • Replaced 15.84 miles of existing overhead wire with new insulated wire
			<del>11/26/2020</del> 11/27/2020	Data not available		
			10/26/2020			
<del>35</del> 38	ED-06432	FINGAL	<del>12/23/2020</del> 12/24/2020			Completed: • Replaced approximately 33.79 miles of existing overhead wire with new insulated wire
			<del>12/7/2020</del> 12/8/2020	Data not available		
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
39	ED-06452	FIREBIRD	12/9/2023		9,037	Completed: • Replaced 17.59 miles of existing overhead wire with new insulated wire
			10/30/2023	15,563		
			10/30/2023	5,912		
36	ED-04170	FROZEN	N/A		Completed: • Replaced <0.1 miles of existing overhead wire with new insulated wire	
			N/A	Data not available		
			N/A			
40	ED-06888	GABBERT	11/25/2021		Completed: • Replaced 2.57 miles of existing overhead wire with new insulated wire	
			11/25/2021	Data not available		
			11/25/2021			
			12/23/2020		Completed:	

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
37 41	ED-07382	GNATCATCHER	12/7/2020	Data not available	<ul style="list-style-type: none"> <li>• New insulated wire has already been installed on nearly all existing overhead portions of the circuit</li> <li>• Replaced an additional 3.53 miles of existing overhead wire with new insulated wire at various locations</li> </ul>	
			<del>12/2/2020</del> 12/3/2020			
			11/27/2020			
			<del>10/29/2019</del> 10/30/2019			
			10/24/2019			
			10/10/2019			
38 42	ED-07742	GUITAR	<del>12/10/2024</del>	4,604	Completed: <ul style="list-style-type: none"> <li>• Replaced 32.46 miles of existing overhead wire with new insulated wire</li> </ul>	
			12/10/2024	109		
			11/6/2024	8,946		
			11/25/2021	Data not available		
			11/22/2021			
			1/19/2021			
			1/19/2021			
			1/15/2021			
			12/23/2020			
			12/3/2020			
			11/27/2020			
			10/26/2020			
			10/30/2019			
			10/28/2019			
10/24/2019						
<del>10/10/2019</del> 10/11/2019						
39 43	ED-08446	HILLFIELD	12/23/2020	Data not available	Completed: <ul style="list-style-type: none"> <li>• Replaced 6.41 miles of existing overhead wire with new insulated wire</li> <li>• Automated 3 switches</li> <li>• Updated switching protocols</li> <li>• Implemented operational protocol for portions of the circuit</li> </ul>	
			12/7/2020			
			10/26/2020			
40 44	ED-08698	HORNTOAD	12/9/2024	2,165	Under engineering review for undergrounding	
					Completed: <ul style="list-style-type: none"> <li>• Install 1 automated switch</li> </ul>	
			11/6/2024	2,706	Planned Work: <ul style="list-style-type: none"> <li>• Install 2 automated switches</li> </ul>	
			10/18/2024	1,200		
			10/30/2019		Completed:	

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
<del>41</del> 45	ED-08795	HUCKLEBERRY	<del>10/27/2019</del> 10/28/2019 10/24/2019 10/10/2019	Data not available	• Replaced 18.27 miles of existing overhead wire with new insulated wire and implement protocols to transfer load to a less affected circuit	
<del>42</del> 46	ED-08880	ICE HOUSE	<del>12/7/2020</del> 12/8/2020 <del>11/26/2020</del> 11/27/2020 10/26/2020	Data not available	Completed: • Replaced 1.08 miles of existing overhead wire with new insulated wire	
<del>43</del> 47	ED-08904	IMPALA	11/25/2021 11/24/2021 11/21/2021 1/19/2021 <del>12/7/2020</del> 12/8/2020 12/3/2020 11/27/2020 10/26/2020 10/26/2020	Data not available	Completed: • Replaced 25.8 miles of existing overhead wire with new insulated wire	
48	ED-10203	LAUDA	<del>12/10/2024</del> 11/6/2024 11/6/2024	25 27 28	Completed: • Replaced 1.75 miles of existing overhead wire with new insulated wire	
<del>44</del> 49	ED-10483	LIMITED	12/17/2024 12/9/2024 11/6/2024 10/18/2024	639 4,159 3,956 9,229	Under engineering review for PSPS grid hardening measures	
50	ED-10485	LIMONITE	12/9/2024 11/7/2024 11/6/2024	75 25 6	Under engineering review for PSPS grid hardening measures	
<del>45</del> 51	ED-10705	LOPEZ	<del>12/7/2020</del> 12/8/2020 12/3/2020 10/26/2020	Data not available	Completed: • Replaced 22.4 miles of existing overhead wire with new insulated wire • Installed 1 automated switch	
<del>46</del> 52	ED-10729	LOUCKS	12/7/2020 11/26/2020 <del>10/26/2020</del> 9/9/2020 10/30/2019 10/28/2019 10/24/2019	Data not available	Completed:	

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers	
			10/10/2019				
47 53	ED-10934	MAGUIRE	12/17/2024	15,439	Under engineering review for PSPS grid hardening measures		
			12/9/2024	27,128			
			11/6/2024	37,577			
48 54	ED-11500	MCKEVETT	10/30/2019	Data not available	Completed: • Implemented operational protocol to raise PSPS windspeed thresholds		
			10/28/2019				
			<del>10/23/2019</del> 10/24/2019				
			10/24/2019				
			<del>10/10/2019</del> 10/11/2019				
55	ED-11695	MERLIN	12/10/2024	22,102	Planned Work: • Replace 14.12 miles of existing overhead wire with new underground cable		
			12/9/2024	10,291			
			11/6/2024	39,153			
49 56	ED-11760	METTLER	12/7/2020	Data not available	Completed: • Replaced 38.0 miles of existing overhead wire with new insulated wire		
			12/7/2020				
			<del>12/2/2020</del> 12/3/2020				
			12/2/2020				
			11/16/2020				
			10/30/2019				
			10/28/2019				
			10/24/2019				
10/10/2019							
50 57	ED-12167	MORA	11/1/2019	Data not available	Completed: • Replaced 4.72 miles of existing overhead wire with new insulated wire		
			10/30/2019				
			10/28/2019				
			<del>10/21/2019</del> 10/24/2019				
			<del>10/2/2019</del> 10/10/2019				
54 58	ED-1354	MORGANSTEIN	12/9/2023	40,481	Under engineering review for PSPS grid hardening measures		
			11/20/2023	12,261			
			10/29/2023	10,370			
			<del>11/24/2021</del> 11/25/2021	Data not available			Completed: • Replace 16.16 miles of existing overhead wire with new insulated wire
			11/21/2021				
			1/19/2021				
59	ED-12482	NAPA	12/8/2020	Data not available	Completed: • Replaced 17.40 miles of existing overhead wire with new insulated wire		
			12/8/2020				
			12/3/2020				

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
			12/3/2020			
52 60	ED-12485	NAPOLEON	12/23/2020	Data not available	Completed: • Replaced 5.8 miles of existing overhead wire with new insulated wire	
			12/8/2020			
			12/7/2020			
			12/3/2020			
			12/2/2020			
53 61	ED-12700	NICHOLAS	12/17/2024	1,786	Under engineering review for undergrounding	
			12/9/2024	3,761		
			<del>11/7/2024</del> 11/6/2024	10,322		
			10/18/2024	4,741		
			9/9/2024	2,119		
			11/20/2023	4,028		
			11/9/2023	2,487		
			10/30/2023	2,714		
			10/29/2023	9,213		
54 62	ED-12847	NORTHPARK	12/10/2024	14,229	Completed: • Replaced 18.6 miles of existing overhead wire with new insulated wire • Implemented switching protocols to transfer load to a less affected circuit • Automated 2 existing sectionalizing devices	
			12/10/2024	125		
			11/6/2024	28,757		
			12/9/2023	100		
			10/30/2023	4,186		
			10/30/2023	170		
			12/24/2020	Data not available		
			12/23/2020			
			12/18/2020			
			<del>12/2/2020</del> 12/3/2020			
			<del>11/26/2020</del> 11/27/2020			
63	ED-13791	PATRICIA	12/8/2020	Data not available	Completed: • Replaced 33.91 miles of existing overhead wire with new insulated wire	
			12/8/2020			
			12/7/2020			
55 64	ED-13918	PENSTOCK	12/12/2024	18	Under engineering review for PSPS grid hardening measures	
			10/18/2024	30	Planned Work:	
			8/17/2024	23	• Install 1 automated switch	
65	ED-13983	PETIT	11/1/2019	Data not available	Planned Work: • Replace 1.21 miles of existing overhead wire with new insulated wire	
			10/30/2019			
			10/28/2019		Completed:	
			10/24/2019		• Replaced 4.81 miles of existing overhead wire with new insulated wire	



SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
56 66	ED-14005	PHEASANT	12/23/2020	Data not available	Completed: • Replaced 9.3 miles of existing overhead wire with new insulated wire • Installed 2 automated switches	
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
57 67	ED-14190	PLATEAU	12/17/2024	1,883	Under engineering review for undergrounding	
			12/9/2024	8,073		
			11/6/2024	19,752		
			10/18/2024	3,758		
			9/9/2024	853		
			<del>11/25/2021</del>	Data not available		
			<del>11/25/2021</del>			
			<del>11/25/2021</del>			
68	ED-14494	PURCHASE	<del>10/30/2019</del>	Data not available	Completed: • Replaced 2.26 miles of existing overhead wire with new insulated wire	
			10/30/2019			
			<del>10/28/2019</del>			
58 69	ED-14603	RACER	12/23/2020	Data not available	Completed: • Replaced 0.6 miles of existing overhead wire with new insulated wire • Implemented operational protocols for portions of the circuit	
			12/7/2020			
			12/3/2020			
59 70	ED-14645	RAINBOW	<del>11/25/2021</del>	Data not available	Completed: • Replaced 15.82 miles of existing overhead wire with new insulated wire • Installed 1 automated switch	
			<del>1/19/2021</del>			
			1/19/2021			
			<del>12/24/2020</del>			
			12/23/2020			
			12/7/2020			
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			<del>10/31/2019</del> 11/1/2019			
			10/30/2019			
			10/28/2019			
			<del>10/28/2019</del>			
10/24/2019						
60 71	ED-14758	RED BOX	12/18/2024	457	Under engineering review for PSPS grid hardening measures	
			<del>12/11/2024</del> 12/9/2024	1,172		
			<del>11/8/2024</del> 11/6/2024	1,436		
			<del>10/19/2024</del> 10/18/2024	788		
			<del>12/7/2020</del> 12/8/2020	Completed: • Installed an additional weather station		
<del>12/2/2020</del> 12/3/2020						

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PPS of circuit [4]	Estimated Annual Decline in PPS Events and PPS Impact on Customers
			10/26/2020 9/9/2020 10/30/2019 <del>10/27/2019</del> 10/28/2019 <del>10/24/2019</del> 10/25/2019	Data not available	• Adjusted switching plans and weather station assignments in order to leverage better situational awareness and reduce PPS use	
<del>64</del> 72	ED-15475	ROWCO	12/9/2024 11/6/2024 10/18/2024	28,413 2,629 37,191	Under engineering review for PPS grid hardening measures	
<del>62</del> 73	ED-15586	RUSTIC	<del>12/2/2020</del> 12/3/2020 11/27/2020 10/26/2020	Data not available	Under engineering review for PPS grid hardening measures  Completed: • Replaced 14.36 miles of existing overhead wire with new insulated wire	
<del>63</del> 74	ED-15618	SADDLEBACK	12/23/2020 12/7/2020 <del>12/2/2020</del> 12/3/2020	Data not available	Completed: • Replaced 3.25 miles of existing bare overhead wire with new insulated wire • Added new weather station near end of the circuit to improve situational awareness	
			12/9/2024 11/6/2024 <del>11/6/2024</del> 10/18/2024 <del>12/9/2023</del> <del>10/29/2023</del> <del>10/29/2023</del> 11/24/2021 <del>11/21/2021</del> 11/22/2021 10/15/2021 9/30/2021 1/19/2021 <del>1/19/2021</del> 1/18/2021	5,430 <del>6,228</del> 3,798 2,534 <del>217</del> 220 313 667 413	Under engineering review for PPS grid hardening measures           Completed: • Replaced 30.3 miles of existing overhead wire with new insulated wire. • Circuit is fully covered with Raised Wind Speed Thresholds • Installed 1 automated switch	

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
64 75	ED-15737	SAND CANYON	1/18/2021	Data not available	<ul style="list-style-type: none"> <li>Identified and increased segmentation for underground portions of the circuit. Updated switching protocols to transfer new segments to an adjacent circuit, mitigating impacts to ~1,800 customers.</li> </ul>	
			1/14/2021			
			1/14/2021			
			12/23/2020			
			12/23/2020			
			12/18/2020			
			12/7/2020			
			12/7/2020			
			12/3/2020			
			11/26/2020			
			11/26/2020			
			11/17/2020			
			10/26/2020			
			10/26/2020			
			9/9/2020			
76	ED-15945	SAVORY	12/8/2020	Data not available	Planned Work: <ul style="list-style-type: none"> <li>Replace 4.49 miles of existing overhead wire with new insulated wire</li> </ul>	
			12/7/2020			
			12/3/2020			
77	ED-16170	SESPE	10/30/2019	Data not available	Completed: <ul style="list-style-type: none"> <li>Replaced 0.62 miles of existing overhead wire with new insulated wire</li> </ul>	
			10/30/2019			
			10/11/2019			
65 78	ED-16404	SHOVEL	12/7/2020	Data not available	Completed: <ul style="list-style-type: none"> <li>Replaced 40.19 miles of existing overhead wire with new insulated wire and implement protocols to transfer load to a less affected circuit</li> </ul>	
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			12/3/2020			
			11/26/2020			
			11/26/2020			
			11/17/2020			
			<del>10/30/2019</del>			
10/26/2020						
9/9/2020						

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
			10/29/2019			
			<del>10/27/2019</del> 10/28/2019			
			10/26/2019			
			10/24/2019			
			10/20/2019			
			10/10/2019			
66 79	ED-16973	STEEL	12/9/2024	954	Completed: • Updated switching protocols to reassign the boundary point between PSPS Segment 1 and Segment 2 • Replaced 6.48 miles of existing overhead wire with new insulated wire	
			11/6/2024	381		
			11/6/2024	750		
			11/25/2021	Data not available		
			11/21/2021			
			10/15/2021			
			1/19/2021			
			12/23/2020			
			12/7/2020			
			12/7/2020			
			<del>12/2/2020</del> 12/3/2020			
			10/30/2019			
			10/28/2019			
			10/24/2019			
10/10/2019						
80	ED-14732	STUBBY	12/9/2024	52	Completed: • Replaced 27.82 miles of existing overhead wire with ne	
			12/9/2024	51		
			11/6/2024	125		
67 81	ED-17383	SUTT	11/24/2021	Data not available	Completed: • 3 frequently impacted segments are 100% covered conductor with Raised Wind Speed Thresholds. • Identified and added segmentation for overhead portions of circuit. Updated switching protocols to increase potential customer mitigations. Mitigations dependent on which weather station(s) reaches de-energization thresholds during an event. Reviewing installation of additional remote isolation device. • Installed new weather station 12/13/2023 for increased situational awareness.	
			11/21/2021			
			1/19/2021			
			12/18/2020			
			<del>12/7/2020</del> 12/8/2020			
			10/26/2020			
			12/17/2024	548	Under engineering review for PSPS grid hardening meas	
			12/10/2024	4,132		

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
68 82	ED-17546	TAHQUITZ	12/9/2024	901	Completed: • Added new weather station near in the Mountain Center area to improve situational awareness	
			11/6/2024	4,812		
			10/30/2019	Data not available		
			10/28/2019			
			10/24/2019			
			<del>10/10/2019</del> 10/11/2019			
83	ED-17487	TAIWAN	12/3/2020	Data not available	Planned Work: • Replace 3.54 miles of existing overhead wire with new insulated wire  Completed: • Replaced 11.76 miles of existing overhead wire with new insulated wire	
			10/26/2020			
			10/26/2020			
			1/1/2019			
			1/1/2019			
			1/1/2019			
69 84	ED-17529	TANAGER	12/7/2020	Data not available	Completed: • Replaced 28.87 miles of existing overhead wire with new insulated wire • Installed 1 new automated switch	
			<del>12/2/2020</del> 12/3/2020			
			11/27/2020			
			10/30/2019			
			10/24/2019			
			10/10/2019			
70 85	ED-17548	TAPO	12/7/2020	Data not available	Completed: • Replaced 11.7 miles of existing overhead wire with new insulated wire • Implemented operational protocol to raise PSPS windspeed thresholds	
			12/3/2020			
			11/26/2020			
			10/26/2020			
86	ED-17880	TIMBER CANYON	11/25/2021	Data not available	Planned Work: • Replace 8.04 miles of existing overhead wire with new insulated wire  Completed: • Replaced 25.87 miles of existing overhead wire with new insulated wire	
			11/25/2021			
			1/19/2021			
74 87	ED-18243	TUBA	11/25/2019	Data not available	Completed: • Replaced 3.18 miles of existing overhead wire with new insulated wire	
			10/30/2019			

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
			10/24/2019		Planned Work: • Replace 4.97 miles of existing overhead wire with new insulated wire	
72 88	ED-18252	TUFA	<del>12/10/2020</del> 12/11/2020 11/17/2020 11/6/2020	Data not available	Completed: • Replaced 9.41 miles of existing overhead wire with new insulated wire  Planned Work: • Replace 11.88 miles of existing overhead wire with new insulated wire	
73 89	ED-18370	TWIN LAKES	12/23/2020 12/7/2020 <del>12/2/2020</del> 12/3/2020 11/27/2020 10/26/2020	Data not available	Completed: • Implemented operational protocol to raise PSPS windspeed thresholds • Implemented switching protocols to isolate overhead portions and transfer customers to adjacent circuits	
74 90	ED-01754	VARGAS	12/23/2020 <del>12/7/2020</del> 12/8/2020 12/3/2020 11/27/2020 10/26/2020	Data not available	Completed: • Replaced 0.2 miles of existing overhead wire with new insulated wire • Installed 1 new automated switch • Implemented operational protocol to raise PSPS windspeed thresholds	
75 91	ED-18650	VERA CRUZ	12/23/2020 12/7/2020 <del>12/2/2020</del> 12/3/2020 10/26/2020	Data not available	Completed: • Replaced 8.52 miles of existing overhead wire with new insulated wire • Implemented switching protocols to update boundary between PSPS segment 1 and segment 2 • Installed an additional weather station • Installed 1 new automated switch	
76 92	ED-19850	ZONE	12/7/2020 <del>12/7/2020</del> 12/7/2020 <del>12/2/2020</del> 12/3/2020 <del>12/3/2020</del> 12/3/2020 10/30/2019	Data not available	Completed:  • Replaced 23.7 miles of existing overhead wire with new insulated wire  • Implemented operational protocols to raise PSPS windspeed thresholds near substation	

SCE corrections to Table 4-3 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Entry #	Circuit ID [1]	Name of Circuit	Dates of Outages [2]	Number of Customers Hours of PSPS per Outage [3]	Measures taken, or planned to be taken, to reduce the need for, and impact of, future PSPS of circuit [4]	Estimated Annual Decline in PSPS Events and PSPS Impact on Customers
			10/28/2019 10/24/2019 10/10/2019		<ul style="list-style-type: none"> <li>• Circuit is fully covered with Raised Wind Speed Thresholds. Identified and added segmentation for overhead portions of circuit. Updated switching protocols to transfer portions to an adjacent circuit. Transfers dependent on which weather station(s) reaches de-energization thresholds during an event.</li> <li>• Installed an additional weather station</li> </ul>	

Table 6-4: SCE Summary of Risk Reduction for Top-Risk Circuits<sup>107</sup>

Circuit, Segment, or Span ID	Initial Overall Utility Risk	2026 Initiative Activities	2026 Overall Utility Risk	2027 Initiative Activities	2027 Overall Utility Risk	2028 Initiatives Activities	2028 Overall Utility Risk
TUNGSTEN	0.79861	<del>Covered Conductor</del> , Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Structure Brushing	0.79861	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Structure Brushing	0.79861	Distribution HFRI Inspections and Remediations, Structure Brushing	0.79861
PHEASANT	3.18451	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	3.18451	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	3.18451	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	3.18451
LOUCKS	1.33272	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.33272	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.33272	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.33272
PASCAL	2.26526	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.26526	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.26526	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.26526
DAVENPORT	12.89816	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	12.89816	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	12.89816	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	12.89816
CERRITO	0.35024	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.35024	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.35024	<del>Covered Conductor, Undergrounding Overhead Conductor</del> , Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.07222
RAYBURN	2.11324	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.11324	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.11324	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.11324
SHOVEL	8.09005	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	8.09005	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	8.09005	<del>Covered Conductor</del> , Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	8.05957
PELONA	0.29890	Transmission Proactive Splice Shunting, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management	0.29890	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management	0.29890	Distribution HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management	0.29890

107 Initial overall utility risk captures risk information as of 3/25/2025. 2026 Overall Risk, 2027 Overall Risk, and 2028 Overall Risk capture estimated risk information as of 12/31 of 2026, 2027, and 2028, respectively, based on forecasted deployment of mitigations presented in this WMP.



SCE corrections to Table 6-4 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Circuit, Segment, or Span ID	Initial Overall Utility Risk	2026 Initiative Activities	2026 Overall Utility Risk	2027 Initiative Activities	2027 Overall Utility Risk	2028 Initiatives Activities	2028 Overall Utility Risk
		Program, Structure Brushing, Dead and Dying Tree Removal		Program, Structure Brushing, Dead and Dying Tree Removal		Program, Structure Brushing, Dead and Dying Tree Removal	
GUFFY	0.78051	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.78051	<del>Covered Conductor</del> ; Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.77745	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.77745
STORES	4.20072	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.20072	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.20072	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.20072
PURCHASE	0.56434	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.56434	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.56434	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.56434
ENERGY	4.45002	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.45002	Remote Controlled Automated Reclosers Settings Update, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.44978	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.44978
ARIEL	0.04900	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.04900	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.04900	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.04900
BODKIN	0.23424	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.23424	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.23424	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.23424
CASCADE	0.90370	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.90370	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.90370	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.90370
IDA	1.34631	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.34631	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.34631	Distribution HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.34631
FINGAL	4.53771	REFCL Ground Fault Neutralizer, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.28455	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.28455	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.28455

SCE corrections to Table 6-4 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Circuit, Segment, or Span ID	Initial Overall Utility Risk	2026 Initiative Activities	2026 Overall Utility Risk	2027 Initiative Activities	2027 Overall Utility Risk	2028 Initiatives Activities	2028 Overall Utility Risk
POPPET FLATS	4.01514	REFCL Ground Fault Neutralizer, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.18252	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.18252	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.18252
STONEMAN	3.19270	Long Span Initiative, Distribution HFRI Inspections and Remediations, Distribution Infrared Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	3.19270	<del>Covered Conductor</del> , Long Span Initiative, Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	3.19269	Long Span Initiative, Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	3.19269
PIONEERTOWN	6.78102	<del>Covered Conductor</del> , REFCL Ground Fault Neutralizer, Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.98328	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.98328	Distribution HFRI Inspections and Remediations, Structure Brushing	2.98328
PICK [2]	4.48935	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.48935	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.48935	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.48935
IRVINGTON	0.02587	Distribution HFRI Inspections and Remediations, Structure Brushing	0.02587	<del>Covered Conductor</del> , Distribution HFRI Inspections and Remediations, Structure Brushing	0.02516	Distribution HFRI Inspections and Remediations, Structure Brushing	0.02516
PICONI	1.99738	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.99738	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.99738	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.99738
SNOWCREEK	0.17684	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.17684	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.17684	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.17684
NUTMEG	0.77035	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.77035	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.77035	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.77035
SCHMIDT	1.44596	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management	1.44596	<del>Covered Conductor</del> , Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.44181	Distribution HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.44181

SCE corrections to Table 6-4 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Circuit, Segment, or Span ID	Initial Overall Utility Risk	2026 Initiative Activities	2026 Overall Utility Risk	2027 Initiative Activities	2027 Overall Utility Risk	2028 Initiatives Activities	2028 Overall Utility Risk
		Program, Structure Brushing, Dead and Dying Tree Removal					
SEAWOLF	0.09392	Distribution HFRI Inspections and Remediations, Structure Brushing	0.09392	Distribution HFRI Inspections and Remediations, Structure Brushing	0.09392	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.09392
ARAPAHO	1.45272	Distribution HFRI Inspections and Remediations, Distribution Infrared Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.45272	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.45272	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.45272
MOAB	0.04860	Distribution HFRI Inspections and Remediations, Structure Brushing	0.04860	Distribution HFRI Inspections and Remediations, Structure Brushing	0.04860	<del>Covered Conductor</del> , Distribution HFRI Inspections and Remediations, Structure Brushing	0.03067
LUISENO	2.60530	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.60530	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.60530	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.60530
BALLOON	0.35909	Distribution HFRI Inspections and Remediations, Distribution Infrared Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.35909	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.35909	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.35909
BOUQUET	2.09672	Transmission Proactive Splice Shunting, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.09672	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.09672	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.09672
CALSPAR	0.02751	Long Span Initiative, Distribution HFRI Inspections and Remediations, Distribution Infrared Scanning, Structure Brushing	0.02750	<del>Covered Conductor</del> , Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.02318	Distribution HFRI Inspections and Remediations, Structure Brushing	0.02318
BIG ROCK	1.17538	Remote Controlled Automated Reclosers Settings Update, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Distribution Infrared Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.17515	Long Span Initiative, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.17515	<del>Covered Conductor</del> , Long Span Initiative, Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	1.16882
STAR ROCK	0.19825	Remote Controlled Automated Reclosers Settings Update, Distribution HFRI Inspections and Remediations, Structure Brushing	0.19821	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.19821	Distribution HFRI Inspections and Remediations, Structure Brushing	0.19821

SCE corrections to Table 6-4 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Circuit, Segment, or Span ID	Initial Overall Utility Risk	2026 Initiative Activities	2026 Overall Utility Risk	2027 Initiative Activities	2027 Overall Utility Risk	2028 Initiatives Activities	2028 Overall Utility Risk
KELLER	0.08733	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Structure Brushing	0.08733	Distribution HFRI Inspections and Remediations, Structure Brushing	0.08733	Distribution HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.08733
CORTESE	0.17324	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.17324	<del>Undergrounding Overhead Conductor,</del> Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.04552	<del>Undergrounding Overhead Conductor,</del> Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.04552
BOOTLEGGER	6.45075	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	6.45075	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	6.45075	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	6.45075
UTE	0.08064	Long Span Initiative, Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.08063	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.08063	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.08063
SOUTHRIDGE	0.03865	<del>Covered Conductor,</del> Distribution HFRI Inspections and Remediations, Structure Brushing	0.03575	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.03575	<del>Covered Conductor,</del> Distribution HFRI Inspections and Remediations, Structure Brushing	0.03575
MOCKINGBIRD	0.56335	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.56335	Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.56335	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.56335
CORONITA	0.03590	Distribution HFRI Inspections and Remediations, Structure Brushing	0.03590	Distribution HFRI Inspections and Remediations, Structure Brushing	0.03590	Distribution HFRI Inspections and Remediations, Structure Brushing	0.03590
ATENTO	2.07503	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.07503	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.07503	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	2.07503
PAWNEE	4.22999	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.22999	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.22999	<del>Covered Conductor,</del> Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	4.22312
INYO LUMBER	0.24229	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.24229	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.24229	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.24229

SCE corrections to Table 6-4 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

Circuit, Segment, or Span ID	Initial Overall Utility Risk	2026 Initiative Activities	2026 Overall Utility Risk	2027 Initiative Activities	2027 Overall Utility Risk	2028 Initiatives Activities	2028 Overall Utility Risk
PARADISE	1.12261	Undergrounding Overhead Conductor, Long Span Initiative, Transmission Proactive Splice Shunting, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Distribution Infrared Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.26892	Undergrounding Overhead Conductor, Long Span Initiative, Distribution HFRI Inspections and Remediations, Transmission HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.23385	<del>Covered Conductor</del> , Long Span Initiative, Distribution HFRI Inspections and Remediations, Transmission Infrared and Corona Scanning, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.23382
PERRIS	0.25347	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.25347	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.25347	Distribution HFRI Inspections and Remediations, Structure Brushing	0.25347
RAMSGATE	0.06834	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.06834	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.06834	Distribution HFRI Inspections and Remediations, Hazard Tree Management Program, Structure Brushing, Dead and Dying Tree Removal	0.06834

[1] This circuit is located in the burn scar area of the Lidia Fire in January 2025.

## SCE corrections to Section 7.2 submitted on June 2<sup>nd</sup>, 2025 shown relative to May 16<sup>th</sup>, 2025 2026-2028 Base WMP Revision 0

In addition, SCE has been and continues to optimize its reliance on automation to streamline management of PSPS events and improve the accuracy and speed of notifications to customers and other stakeholders.

### 7.2 Frequently De-Energized Circuits

*The narrative must summarize how the electrical corporation will reduce the need for, and impact of, future PSPS implementation on circuits that have been frequently deenergized, as listed in Table 4-3 in Section 4.3.*

Table 4-3 in Section 4.3 (the fully populated version of the table is in Appendix F) identifies SCE's 76 "Frequently De-energized Circuits," which are defined as circuits that have had three or more PSPS events per calendar year.

SCE has already implemented several of the mitigation measures described in Section 7.1 to mitigate the impacts of PSPS events on these circuits. This includes:

- **Covered Conductor:** SCE has installed nearly ~~800~~ 1000 miles of insulated conductor on ~~57~~ 69 of the circuits.
- **RARs and RCS:** SCE has upgraded or installed more than 30 automated switches on more than 20 circuits.
- **Weather Stations:** SCE has installed new weather stations to improve situational awareness for 13 of the circuits.

In addition, SCE has implemented PSPS protocols to raise the PSPS windspeed thresholds for nine of the circuits based on new covered conductor installation and some exceptions for bare conductor circuits with minimal risk. SCE has also updated switching protocols to enable customer load to be transferred to adjacent circuits for twelve of the Frequently De-Energized Circuits.

To further reduce the need for, and impact of, future PSPS events on these circuits, SCE will implement the following mitigation measures during the 2026-2028 timeframe to try to reduce the frequency, duration, and scope of PSPS events on the Frequently De-Energized Circuits:

- **Covered Conductor:** SCE plans to install nearly ~~45~~ 80 miles of insulated conductor on ~~6~~ 12 circuits.
- **RARs and RCS:** Upgrade or install six automated switches on five circuits.

SCE expects to implement additional circuit segmentation. In addition, ~~21~~ 22 circuits are undergoing engineering review to determine potential PSPS grid hardening measures.

### 7.3 Lessons Learned Since 2023-2025 WMP

*Furthermore, the narrative should describe any lessons learned for PSPS events occurring since the electrical corporation's last WMP submission and overall impacts to mitigation methodology in terms of reducing PSPS events in the future.*